


1
FA7 **Fire Alarm Plan - First Floor**
SCALE: 1/8"=1'-0" 2-5 CLASSROOM WING

FIRE ALARM RENOVATION KEY NOTES:

- SEE ELEVATOR PIT DETAIL SHEET E6.2 FOR SMOKE AND HEAT DETECTOR INSTALLATION DETAILS.
- INSTALL RELAY FOR SMOKE DAMPER HARDWIRED FROM ADDRESSABLE CONTROL MODULE. COORDINATE EXACT LOCATION WITH SMOKE DAMPER.
- INSTALL ADDRESSABLE CONTROL MODULES. CONTROL MODULES SHALL BE HARDWIRED TO 24V RELAYS AT SMOKE DAMPER. CONTROL MODULES SHALL HAVE LEDS INDICATING NORMAL AND ALARM CONDITIONS AND SHALL BE PROGRAMMED TO ACTUATE DAMPER VIA RELAY UPON GENERAL ALARM CONDITION.

BY PERMISSION OF ENGINEER ON RECORD, CONTRACTOR MAY USE A CONTROL RELAY MODULE IN LEIU OF CONTROL MODULE AND RELAY TO ACHIEVE SAME CONDITIONS.



KEY PLAN
SCALE: N.T.S. NORTH

THE PYROCADD COMPANY, LLC
A FIRE SYSTEM DESIGN FIRM
P.O. Box 51357
Myrtle Beach, SC 29579
www.pyrocadd.com

PHONE: Myrtle Beach 843-745-8558
Raleigh, NC 919-212-7783
Tel Fax 888-650-8417

EMAIL: PYROCADD@GMAIL.COM

PIEDMONT FIRE PROTECTION SYSTEMS

3609 Bastion Lane
Raleigh, NC 27604

Tel: 919.212.2356
Fax: 919.212.2357

www.piedmontfire.com

Drawing Title	FLOOR PLAN
Project No.	10-102-31
Drawn By	DMR
Scale	N/A
Date	5-12-10
PIR Date	
Revisions	

Job: Durham Elem. School-E
1470 Old Oxford Rd
DURHAM, NC

Contractor: